



Construction

Features:

- Schedule 40 1 1/4" Aluminum Pipe Construction
- 2" Diameter Leveling Foot w/ 2" Fine Adjustment
- · Non-Marring Neoprene Foot Pad

Options:

- · Sold in Sets of Four or Individually
- · Replacement Foot Pad & Insert Sold Separately
- · Custom Heights Available
- · Clamp Required Over 24"
- · Leg Braces Required over 36"

Heights/ Weights:

Set of 4 / 4"	Legs 1 lbs.	Set of 4 / 28" Legs	8 lbs.
Set of 4 / 6"	Legs 2 lbs.	Set of 4 / 30" Legs	9 lbs.
Set of 4 / 8"	Legs 3 lbs.	Set of 4 / 32" Legs	10 lbs.
Set of 4 / 12"	Legs 4 lbs.	Set of 4 / 40" Legs	12 lbs.
Set of 4 / 16"	Legs 5 lbs.	Set of 4 / 48" Legs	14 lbs.
Set of 4 / 24"	Legs 7 lbs.	Set of 4 / 56" Legs	18 lbs.



Empty Leg Receiver



Fixed Height Leg Inserted into Leg Receiver



4' x 4' HaircellPoly Deck with Fixed Height Legs





